

(19)

Europäisches Patentamt
European Patent Office
Office européen des brevets



(11)

EP 1 334 824 A2

(12)

EUROPEAN PATENT APPLICATION

(43) Date of publication:
13.08.2003 Bulletin 2003/33

(51) Int Cl.7: **B41C 1/10**, B41N 3/06,
G03F 7/32

(21) Application number: **03002831.0**

(22) Date of filing: **07.02.2003**

(84) Designated Contracting States:
AT BE BG CH CY CZ DE DK EE ES FI FR GB GR
HU IE IT LI LU MC NL PT SE SI SK TR
Designated Extension States:
AL LT LV MK RO

(30) Priority: **08.02.2002 JP 2002032917**
25.02.2002 JP 2002047985

(71) Applicant: **FUJI PHOTO FILM CO., LTD.**
Kanagawa-ken (JP)

(72) Inventor: **Nagase, Hiroyuki**
Yoshida-Cho, Haibara-Gun, Shizuoka-Ken (JP)

(74) Representative: **Grünecker, Kinkeldey,**
Stockmair & Schwanhäusser Anwaltssozietät
Maximilianstrasse 58
80538 München (DE)

(54) **Image forming method**

(57) An image forming method has the steps of exposing a negative type image forming material to infrared laser imagewise, which image forming material includes a substrate and an image recording layer formed thereon, containing a radical generator, a radical-polymerizable compound, an infrared absorbing agent, and a binder polymer; and developing the image forming material with an alkaline developing solution containing at least one nonionic aromatic ether based surfactant of

formula: $X-Y-O-(A)_n-(B)_m-H$ wherein X is an aromatic ring; Y represents a single bond or an alkylene group having 1 to 10 carbon atoms; A and B, which are different from each other, represent $-CH_2CH_2O-$ or $-CH_2CH(CH_3)O-$; and n and m each represent 0 or an integer of from 1 to 100, provided that n and m are not 0 at the same time.

EP 1 334 824 A2

Description**FIELD OF THE INVENTION**

5 [0001] The present invention relates to an image forming method using a negative type image forming material, capable of achieving direct plate making, that is, making a printing plate directly by exposing the image forming material to infrared laser scanning based on digital signals from computers or the like.

BACKGROUND OF THE INVENTION

10 [0002] A recent development in the field of lasers has been significant, and in particular, it has become easy to obtain high-powered, small-sized laser devices that can emit light of wavelengths ranging from a near infrared region to an infrared region. Such laser devices are remarkably useful as light sources for recording in "computer-to-plate" technology, which will be hereinafter referred to as "CTP", which allows the transfer of digital data from computers or the like directly to image forming materials so as to make printing plates. For example, currently available solid lasers and semiconductor lasers capable of infrared radiation within a wavelength range from 760 to 1200 nm have the advantage of very high output power within the above-mentioned wavelength range. In recent years, therefore, there is an increasing demand for an image forming material that has high sensitivity to such lasers, namely, that can greatly change its solubility in a developing solution after exposed to such lasers.

20 [0003] As such an image forming material recordable with infrared lasers, an image forming material capable of inducing radical addition polymerization is conventionally proposed. Typically, image formation can be achieved by imagewise exposing the image forming material to laser light, and developing the image forming material using an alkaline aqueous solution. In such an image formation process, there are two methods: one is to conduct a heat treatment after irradiation of the laser beam, and the other is to start the development immediately after the light exposure without any heat treatment. The former has the shortcomings that a system to carry out the method tends to increase in size and cost because installation of a heating oven is required in an automatic processor for development. On the other hand, one major drawback to the latter method, i.e., non-heating method is that the radical polymerization cannot be accelerated because of the absence of a heating step. As a result, portions exposed to the laser beams cannot be cured sufficiently, so that the printing durability of printing plates made by the latter method is inferior to that by the former method including the heating step. However, the fact that there is no need to set a heating oven in the latter method brings about significant advantages to the users, so that an improved non-heating method has been expected.

30 [0004] To impart sufficient printing durability to the printing plate made by the non-heating method, it is desired to minimize the damage to be applied to image portions in the image forming material in the course of development. For instance, JP KOKAI No. Hei 8-108621 discloses a negative type image forming material comprising a photopolymerizable composition, which is used in combination with a strong alkaline aqueous solution with a pH value of 12.5 or more containing, for example, potassium silicate. Such a developing solution of high pH value tends to impair the image portions formed in the image forming material, which will unfavorably lower the printing durability of the printing plate to be obtained. In addition, there is a drawback that components constituting the image forming material are accumulated and deposited on a developer tank during repeated operations for a long time, thereby clogging the valves or the like.

40 [0005] WO 00/48836 discloses a negative type image forming material comprising a photopolymerizable composition, which image forming material is used in combination with an alkaline aqueous solution containing an alkali such as diethanolamine. This type of developing solution containing an amine such as diethanolamine shows a relatively low pH value, so that the developing solution absorbs less carbon dioxide contained in the air when set in the automatic processor. The result is that deterioration in the activity of the developing solution with time can be minimized. However, the resolution of images to be obtained through development with such a developing solution is disadvantageously low.

SUMMARY OF THE INVENTION

50 [0006] Accordingly, it is an object of the present invention to provide an image forming method using a negative type image forming material capable of recording images therein by irradiation of infrared laser, wherein an image area to be formed in the image forming material can exhibit sufficient strength and excellent resolution even though any heat treatment is not carried out after the irradiation of infrared laser. To be more specific, the object of the present invention is to provide the image forming method capable of imparting excellent printing durability and high resolution to the image portion formed in the image forming material although the method does not include any heat treatment after light exposure; and maintaining a stable operation for an extended period of time by reducing the deterioration of the developing performance with time caused by the change in properties of a developing solution to be employed and minimizing the amount of developing sludge which is accumulated and deposited on a developer tank during the rep-

etition of development.

[0007] The inventor of the present invention has focused attention on the combination of a negative type image forming material and the properties of a developing solution. As a result of an extensive study, it has been found that the above-mentioned object can be achieved by using a developing solution comprising a particular nonionic surfactant.

The present invention has been thus accomplished.

[0008] Namely, the present invention provides an image forming method comprising the steps of exposing a negative type image forming material to infrared laser imagewise, which image forming material comprises a substrate and an image recording layer formed thereon, comprising (A) a radical generator, (B) a radical-polymerizable compound, (C) an infrared absorbing agent, and (D) a binder polymer; and developing the image forming material with an alkaline developing solution comprising at least one nonionic aromatic ether based surfactant represented by the following formula:



wherein X is an aromatic ring; Y represents a single bond or an alkylene group having 1 to 10 carbon atoms; A and B, which are different from each other, represent $-CH_2CH_2O-$ or $-CH_2CH(CH_3)O-$; and n and m each represent 0 or an integer of from 1 to 100, provided that n and m are not 0 at the same time.

[0009] The developing solution comprising the compound represented by the above formula has been found to exhibit excellent developing performance even though the developing solution is within a relatively low pH range where the developing solution is unsusceptible to carbon dioxide gas, to improve the printing durability by reducing the damage applied to the image area, and to enhance the resolution of the obtained image significantly. In addition, it has been found that the developing solution for use in the present invention can work to improve the dispersion properties of insoluble components separated from the image recording layer of the image recording material. This can advantageously contribute to the decrease of developing sludge in a developer tank even though the development is repeated for an extended period of time.

DETAILED DESCRIPTION OF THE INVENTION

[0010] Hereinafter the image forming method according to the present invention will be explained in detail. Firstly, the alkaline developing solution used in the present invention will be explained.



[Developing Solution]

[0011] The image forming method according to the present invention is characterized by the alkaline developing solution used in development, and particularly the nonionic aromatic ether based surfactant used therein, which has a specific structure.

(Nonionic Aromatic Ether Based Surfactant)

[0012] In the compound of the above formula, the aromatic group represented by X in the formula includes phenyl, naphthyl, and anthranyl groups. These aromatic groups may have a substituent. In the formula, when both A and B exist, they may arrayed in the form of a random or block copolymer.

[0013] The compound represented by the above formula includes the compounds represented by the following formula (I-A) or (I-B).



wherein R_1 and R_2 each represents hydrogen atom or an organic residue having 1 to 100 carbon atoms; p and q each

5

10

15

20









25

30

25

25





10

15

20

25








30

35


40

45


55



10




15



20

25



30

[illegible]

35

[0021] The alkaline developing solution used in the present invention is an alkaline aqueous solution having a pH of from 10.0 to 12.8, which comprises at least one of the above nonionic aromatic ether based surfactant.

40

[0022] An alkaline agent which is usable in the developing solution includes inorganic alkaline agents such as sodium tertiary phosphate, potassium tertiary phosphate, ammonium tertiary phosphate, sodium carbonate, potassium carbonate, ammonium carbonate, sodium bicarbonate, potassium bicarbonate, ammonium bicarbonate, sodium borate, potassium borate, ammonium borate, sodium hydroxide, potassium hydroxide, ammonium hydroxide, lithium hydroxide and the like. The alkaline agent which is usable also includes organic alkaline agents such as monomethylamine, dimethylamine, trimethylamine, monoethylamine, diethylamine, triethylamine, monoisopropylamine, diisopropylamine, triisopropylamine, n-butylamine, monoethanolamine, diethanolamine, triethanolamine, monoisopropanolamine, diisopropanolamine, ethyleneimine, ethylenediamine, pyridine, tetramethylammonium hydroxide and the like.

[0023] The above alkaline agent may be used alone or in combination.

50

(Chelating Agent)

55

[0024] The developing solution used in the present invention may comprise a chelating agent. Such chelating agent includes polyphosphates such as $\text{Na}_2\text{P}_2\text{O}_7$, $\text{Na}_5\text{P}_3\text{O}_{10}$, $\text{Na}_3\text{P}_3\text{O}_9$, $\text{Na}_2\text{O}_4\text{P}(\text{NaO}_3\text{P})\text{PO}_3\text{Na}_2$ and Calgon (trade name of sodium polymetaphosphate, available from Calgon Inc. (USA)); polyaminocarboxylic acids and salts thereof such as ethylenediaminetetraacetic acid and potassium and sodium salts thereof, diethylenetriaminepentaacetic acid and potassium and sodium salts thereof, triethylenetetraminehexaacetic acid and potassium and sodium salts thereof, hydroxyethylethylenediaminetriacetic acid and potassium and sodium salts thereof, nitrilotriacetic acid and potassium and sodium salts thereof, 1,2-diaminocyclohexanetetraacetic acid and potassium and sodium salts thereof and 1,3-di-

amino-2-propanoltetraacetic acid and potassium and sodium salts thereof; and organophosphonic acids, potassium, sodium and ammonium salts thereof such as 2-phosphonobutane tricarboxylic acid-1,2,4 and potassium and sodium salts thereof, 2-phosphonobutanone tricarboxylic acid-2,3,4 and potassium and sodium salts thereof, 1-phosphonoethane tricarboxylic acid-1,2,2 and potassium and sodium salts thereof, 1-hydroxyethane-1,1-diphosphonic acid and potassium and sodium salts thereof and amino tri(methylene phosphonic acid) and potassium and sodium salts thereof. The optimum amount of the chelating agent varies depending on the hardness and the amount of hard water used, but the amount thereof in general ranges from 0.01 to 5% by weight and preferably 0.01 to 0.5% by weight in the developing solution practically used.

(Surfactant)

[0025] The developing solution used in the present invention may further comprise a surfactant other than the above-mentioned nonionic aromatic ether based surfactant. Examples of such surfactants are a nonionic surfactant including polyoxyethylene alkylethers such as polyoxyethylene laurylether, polyoxyethylene cetylether and polyoxyethylene stearylether; polyoxyethylene alkylesters such as polyoxyethylene stearate; and sorbitan alkylesters such as sorbitan monolaurate, sorbitan monostearate, sorbitan distearate, sorbitan monooleate, sorbitan sesquioleate and sorbitan trioleate; monoglyceride alkylesters such as glycerol monostearate and glycerol monooleate; an anionic surfactant including alkylbenzene sulfonic acid salts such as sodium dodecylbenzenesulfonate; alkyl naphthalene sulfonic acid salts such as sodium butyl naphthalenesulfonate, sodium pentyl naphthalenesulfonate, sodium hexyl naphthalenesulfonate and sodium octyl naphthalenesulfonate; alkylsulfuric acid salts such as dodecyl sodium sulfate; alkyl sulfonic acid salts such as sodium dodecylsulfonate; and sulfosuccinate salts such as dilauryl sodium sulfosuccinate; and an amphoteric surfactant including alkylbetaines such as laurylbetaine and stearylbetaine; and amino acids type-amphoteric surfactants, and preferred among these are anionic surfactants such as alkyl naphthalene sulfonic acid salts and the like. The surfactant may be used alone or in any combination of at least two of them. The amount of the surfactant in the developing solution ranges generally from 0.1 to 20% by weight in terms of the effective component thereof.

(Others)

[0026] The developing solution used in the present invention may further comprise as occasion demands, other components than those described above. Such components include organic carboxylic acids such as benzoic acid, phthalic acid, p-ethyl benzoic acid, p-n-propyl benzoic acid, p-isopropyl benzoic acid, p-n-butyl benzoic acid, p-t-butyl benzoic acid, p-2-hydroxyethyl benzoic acid, decanoic acid, salicylic acid, 3-hydroxy-2-naphthoic acid and the like; organic solvents such as isopropyl alcohol, benzyl alcohol, ethyl cellosolve, butyl cellosolve, phenyl cellosolve, propylene glycol, diacetone alcohol and the like; a reducing agent; a colorant dye; a pigment; a water softener; an antiseptic agent and the like.

[0027] The above mentioned developing solution can be used as a developing solution or a replenisher for development of a negative type image forming material, and is preferably applied to an automatic processor. When an automatic processor is used to perform development procedure, the developing solution becomes exhausted depending on throughput amount of materials processed, and a replenisher or a fresh developing solution may be used to restore the throughput capacity of developing solution. Specifically, when a replenisher which has the higher concentration of a bicarbonate than those in an initial developing solution is supplied to the developing solution, the more amount of image forming material can be processed with no need to exchange of the developing solution in a developer tank for a long period of time. This manner of using the replenisher may be preferably applied to the image forming method of the present invention.




[0028] An image forming material for use with the image forming method of the present invention comprises a substrate and an image recording layer formed thereon, comprising (A) a radical generator, (B) a radical-polymerizable compound, (C) an infrared absorbing agent, and (D) a binder polymer. When such an image forming material is imaged by exposure to infrared laser beams, one portion of the image recording layer exposed to the infrared laser absorbs the laser light and convert light into heat energy owing to the function of the infrared absorbing agent (C) contained in the image recording layer. By the application of heat thus generated, the radical generator (A) also contained in the image recording layer is decomposed to generate radicals, which induce a reaction of the radical-polymerizable compound (B) and the binder polymer (D). The above-mentioned light-exposed portion is thus cured to be an image area. The other portion not exposed to infrared laser beams is not cured, so that the non-cured portion is removed from the image forming material when the image forming material is developed with the previously mentioned alkaline developing solution. The latter portion becomes a non-image area.

[0029] Each of the components constituting the image recording layer will now be explained in detail.

(A) Radical generator

[0030] The radical generator for use in the present invention is a compound that can generate radicals upon irradiation of infrared laser, when used in combination with the infrared absorbing agent (C). Examples of the radical generator include onium salts, s-triazine compounds having a trihalomethyl group, peroxides, azo based polymerization initiators, azido compounds, and borate salts. In particular, the onium salts are preferable because they have high sensitivity. Specific examples of the onium salts are iodonium salts, diazonium salts, and sulfonium salts. These onium salts do not serve as an acid generator, but a radical polymerization initiator.

[0031] Among the above-mentioned onium salts which are suitably used in the present invention are the following onium salts represented by formulas (1) to (3).












[0032] In the above formula (1), Ar¹¹ and Ar¹² are each independently an aryl group having 20 carbon atoms or less which may have a substituent. Preferable examples of the substituent for the aryl group include a halogen atom, nitro group, an alkyl group having 12 carbon atoms or less, an alkoxy group having 12 carbon atoms or less, and an aryloxy group having 12 carbon atoms or less. Z¹¹⁻ represents a counter ion such as a halogen ion, perchlorate ion, tetrafluoroborate ion, carboxylate ion, hexafluorophosphate ion, or sulfonate ion. Preferably used are perchlorate ion, carboxylate ion, and arylsulfonate ion.








[0033] In the above formula (2), Ar²¹ is an aryl group having 20 carbon atoms or less which may have a substituent. Preferable examples of the substituent for the aryl group include a halogen atom, nitro group, an alkyl group having 12 carbon atoms or less, an alkoxy group having 12 carbon atoms or less, an aryloxy group having 12 carbon atoms or less, an alkylamino group having 12 carbon atoms or less, a dialkylamino group having 12 carbon atoms or less, an arylamino group having 12 carbon atoms or less, and a diarylamino group having 12 carbon atoms or less. Z²¹⁻ represents the same counter ion as previously defined in Z¹¹⁻.







[0034] In the above formula (3), R³¹, R³², and R³³, which may be the same or different, are each a hydrocarbon group having 20 carbon atoms or less which may have a substituent. Preferable examples of the substituent for the hydrocarbon group include a halogen atom, nitro group, an alkyl group having 12 carbon atoms or less, an alkoxy group having 12 carbon atoms or less, and an aryloxy group having 12 carbon atoms or less. Z³¹⁻ represents the same counter ion as previously defined in Z¹¹⁻.






[0035] Specific examples of the onium salts preferably used in the present invention are shown below.














[0036] It is preferable that the radical generator for use in the present invention have a maximum absorption wavelength of 400 nm or less, and more preferably 360 nm or less. When the radical generator for use in the image recording layer exhibits an absorption wavelength within the ultraviolet region, the image forming material can be handled under white light.

[0037] The amount of the radical generator is suitably in the range of 0.1 to 50% by weight, preferably 0.5 to 30% by weight, and more preferably 1 to 20% by weight, based on a total solid content of a coating liquid for the image recording layer. When the amount of the radical generator is less than 0.1% by weight, the sensitivity is lowered. On the other hand, when the amount of the radical generator exceeds 50% by weight, a non-image area is contaminated during printing. The above-mentioned radical generators may be used alone or in combination. Further, the radical generator may be contained in a single image recording layer together with other components. Alternatively, the image forming material may further comprise an additional layer where the radical generator is contained.

(B) Radical-polymerizable compound

[0038] The radical-polymerizable compound for use in the present invention is a compound having at least one ethylenically unsaturated double bond, which compound is selected from the compounds having at least one, preferably two or more terminal ethylenically unsaturated double bonds. Such compounds are well known in the art, and any compounds can be used in the present invention without any limitation. The radical-polymerizable compound is in the form of a monomer, prepolymer, that is, a dimer, trimer or oligomer, a mixture thereof, or a copolymer of the above monomers. Examples of such monomers and copolymers of the monomers include unsaturated carboxylic acids such as acrylic acid, methacrylic acid, itaconic acid, crotonic acid, isocrotonic acid, and maleic acid, and esters and amides thereof. Preferably used are ester compounds of an unsaturated carboxylic acid and an aliphatic polyhydric alcohol and amide compounds of an unsaturated carboxylic acid and an aliphatic polyvalent amine. In addition, also preferably used are an unsaturated carboxylic acid ester having a nucleophilic substituent such as a hydroxyl group, an amino group or a mercapto group or the like; an addition reaction product of amides and monofunctional or polyfunctional isocyanates, or epoxys; a dehydration condensation reaction product of amides and a monofunctional or polyfunctional carboxylic acid and the like. Further, as the preferable radical-polymerizable compounds, there can be mentioned an addition reaction product of an unsaturated carboxylic acid esters or amides having an electrophilic substituent, such as an isocyanate group or an epoxy group, and monofunctional or polyfunctional alcohols, amines or thiols, and further, a substitution reaction product of an unsaturated carboxylic acid esters or amides having an elimination substituent such as a halogen group or a tosyloxy group and a monofunctional or polyfunctional alcohols, amines or thiols. Similarly, the reaction products obtained by using unsaturated phosphonic acid or styrene instead of the above-mentioned unsaturated carboxylic acid can also be used.

[0039] Specific examples of the esters of aliphatic polyhydric alcohol compounds and unsaturated carboxylic acids, which constitute a group of preferable radical-polymerizable compounds, are as follows:

acrylic esters such as ethylene glycol diacrylate, triethylene glycol diacrylate, 1,3-butanediol diacrylate, tetramethylene glycol diacrylate, propylene glycol diacrylate, neopentyl glycol diacrylate, trimethylolpropane triacrylate, trimethylolpropane tri(acryloyloxypropyl) ether, trimethylethane triacrylate, hexanediol diacrylate, 1,4-cyclohexanediol diacrylate, tetraethylene glycol diacrylate, pentaerythritol diacrylate, pentaerythritol triacrylate, pentaerythritol tetraacrylate, dipentaerythritol diacrylate, dipentaerythritol hexaacrylate, sorbitol triacrylate, sorbitol tetraacrylate, sorbitol pentaacrylate, sorbitol hexaacrylate, tri(acryloyloxyethyl) isocyanurate, and polyester acrylate oligomer;

methacrylic esters such as tetramethylene glycol dimethacrylate, triethylene glycol dimethacrylate, neopentyl glycol dimethacrylate, trimethylolpropane trimethacrylate, trimethylethane trimethacrylate, ethylene glycol dimethacrylate, 1,3-butanediol dimethacrylate, hexanediol dimethacrylate, pentaerythritol dimethacrylate, pentaerythritol trimethacrylate, pentaerythritol tetramethacrylate, dipentaerythritol dimethacrylate, dipentaerythritol hexamethacrylate,

ylate, sorbitol trimethacrylate, sorbitol tetramethacrylate, bis[p-(3-methacryloxy-2-hydroxypropoxy)phenyl]dimethylmethane, and bis[p-(methacryloxyethoxy)phenyl] dimethylmethane;
 itaconates such as ethylene glycol diitaconate, propylene glycol diitaconate, 1,3-butanediol diitaconate, 1,4-butanediol diitaconate, tetramethylene glycol diitaconate, pentaerythritol diitaconate, and sorbitol tetraitaconate;
 crotonates such as ethylene glycol dicrotonate, tetramethylene glycol dicrotonate, pentaerythritol dicrotonate, and sorbitol tetradicrotonate;
 isocrotonates such as ethylene glycol diisocrotonate, pentaerythritol diisocrotonate, and sorbitol tetraisocrotonate;
 and
 maleates such as ethylene glycol dimaleate, triethylene glycol dimaleate, pentaerythritol dimaleate, and sorbitol tetramaleate.

[0040] Other examples of the esters include aliphatic alcohol based esters as disclosed in JP KOKOKU No. Sho 46-27926, JP KOKOKU No. Sho 51-47334, and JP KOKAI No. Sho 57-196231; esters with an aromatic skeleton as disclosed in JP KOKAI No. Sho 59-5240, JP KOKAI No. Sho 59-5241, and JP KOKAI No. Hei 2-226149; and amino-group containing esters as disclosed in JP KOKAI No. Hei 1-165613.

[0041] Examples of the above-mentioned amide monomers prepared from the aliphatic polyvalent amine compounds and unsaturated carboxylic acids include methylenebis-acrylamide, methylenebis-methacrylamide, 1,6-hexamethylenebis-acrylamide, 1,6-hexamethylenebis-methacrylamide, diethylenetriamine trisacrylamide, xylylenebisacrylamide, and xylylenebismethacrylamide.

[0042] Other examples of the amide monomers preferably used in the present invention are amide monomers having a cyclohexylene structure as disclosed in JP KOKOKU No. Sho 54-21726.

[0043] In addition, urethane based addition-polymerizable compounds prepared by addition reaction of isocyanate with hydroxyl group are suitably used in the present invention. More specifically, there can be mentioned vinyl urethane compounds having two or more polymerizable vinyl groups in a molecule thereof, which is disclosed in JP KOKOKU No. Sho 48-41708, prepared by adding a hydroxyl-group containing vinyl monomer represented by the following formula (4) to a polyisocyanate compound having two or more isocyanate groups in a molecule thereof:



wherein R^{41} and R^{42} each represent H or CH_3 .

[0044] In addition to the above, also suitably used are urethane acrylate compounds which are disclosed in JP KOKAI No. Sho 51-37193 and JP KOKOKU No. Hei 2-32293 and JP KOKOKU No. Hei 2-16765; and urethane compounds having an ethylene oxide skeleton which are disclosed in JP KOKOKU Nos. Sho 58-49860, 56-17654, 62-39417, and 62-39418.

[0045] Another suitable class of radical-polymerizable compounds comprises radical-polymerizable compounds having an amino structure or sulfide structure in the molecule thereof as disclosed in JP KOKAI No. Sho 63-277653, JP KOKAI No. Sho 63-260909 and JP KOKAI No. Hei 1-105238.

[0046] Also, there can be mentioned polyfunctional acrylates and methacrylates such as polyester acrylates and epoxy acrylates obtained from a reaction of epoxy resin and (meth)acrylic acid as described in JP KOKAI No. Sho 48-64183, JP KOKOKU No. Sho 49-43191 and JP KOKOKU No. Sho 52-30490. Further, particular unsaturated compounds disclosed in JP KOKOKU Nos. Sho 46-43946, Hei 1-40337, and Hei 1-40336; and vinylphosphonic acid compounds disclosed in JP KOKAI No. Hei 2-25493 can also be used as the radical-polymerizable compounds. Moreover, a structure containing a perfluoroalkyl group disclosed in JP KOKAI No. Sho 61-22048 may also be preferably employed in the present invention. The compounds referred to as photocurable monomers and oligomers in "Journal of the Adhesion Society of Japan" vol. 20, No. 7, pp 300 - 308 (1984) can also be used in the present invention.

[0047] It may be freely determined according to the final design for the performance of the image forming material which structure is selected for the radical-polymerizable compound, whether the above-mentioned radical-polymerizable compounds are used alone or in combination, what the amount of radical-polymerizable compounds is, and the like. For instance, the radical-polymerizable compounds may be determined in consideration of the following viewpoints. The more the number of unsaturated groups contained in one molecule in the structure, the more preferable in terms of sensitivity. In most cases, compounds having a functionality of two or more are preferable. Further, to improve the strength of the image area, that is, the cured film portion, compounds with a functionality of three or more are preferably used. Furthermore, the combination of the compounds with different functionalities and different polymerizable groups, which may be selected, for example, from acrylic ester compounds, methacrylic ester compounds, and styrene compounds, is effective for controlling both the photosensitivity and the strength of the image recording layer. Radical-polymerizable compounds having a high molecular weight and a strong hydrophobic nature tend to

retard the developing speed and precipitate in the employed developing solution although excellent sensitivity and sufficient film strength can be obtained.

[0048] Selection of appropriate radical-polymerizable compound(s) and proper use of those compounds in the image recording layer become important factors in determining the compatibility of the radical-polymerizable compound(s) with other components contained in the image recording layer, e.g., a binder polymer, initiator, coloring agent and the like, and the dispersion properties of those components. For example, the use of a radical-polymerizable compound with low purity and the combination of two or more compounds can contribute to the increase in compatibility with other components. A particular structure may be adopted for the purpose of improving the adhesion of the image recording layer to the substrate or an overcoating layer to be provided on the image recording layer.

[0049] As the content of the radical-polymerizable compound in the image recording layer increases, the sensitivity can advantageously improve. However, an excessive amount of radical-polymerizable compound produces problems, for example, unfavorable phase separation. Further, there occurs another problem in the process of manufacture of the image forming material, to be more specific, transfer of the components contained in the image recording layer, and defective production because of increased adhesion of the image recording layer. In addition to the above, an excessive amount of radical-polymerizable compound causes precipitation in a developing solution to be employed.

[0050] In light of the above-mentioned points, the amount of the radical-polymerizable compound is suitably in the range of 5 to 80% by weight, preferably 20 to 75% by weight, based on the total weight of the composition of the image recording layer.

[0051] As mentioned above, those radical-polymerizable compounds may be used alone or in combination. The radical-polymerizable compounds may be freely determined in terms of structure, combination and amount to be added, with consideration given to the degree of inhibition against the polymerization due to oxygen, the resolution of the obtained image, the fogging properties, and a change in refractive index, and the surface tackiness of the obtained image recording layer. Furthermore, the image recording layer may be prepared by a multi-layered structure or a coating method for them, such as an undercoating or top coating, if required.

(C) Infrared absorbing agent

[0052] According to the image forming method of the present invention, image recording can be achieved by irradiation of infrared laser, so that the infrared absorbing agent is essential in the image recording layer. The infrared absorbing agent works to absorb the infrared light and convert it into heat energy. Due to heat thus generated, the radical generator is decomposed to generate radicals. The infrared absorbing agent for use in the present invention comprises dyes and pigments having a maximum absorption within a wavelength range from 760 to 1200 nm.


[0053] As the dyes suitably used as the infrared absorbing agent in the present invention, commercially available conventional dyes, and other dyes, for example, as mentioned in literatures such as "Handbook of Dyes", edited by The Society of Synthetic Organic Chemistry, Japan (1970) can be used. More specifically, preferably employed are dyes as listed in JP KOKAI No. Hei 10-39509 (in paragraphs [0050] and [0051]), e.g., azo dyes, metal complex azo dyes, pyrazolone azo dyes, naphthoquinone dyes, anthraquinone dyes, phthalocyanine dyes, carbonium dyes, quinoneimine dyes, methine dyes, cyanine dyes, squarylium dyes, pyrylium salts, and metal thiolate complexes.

[0054] Preferable examples of the dyes serving as the infrared absorbing agents include cyanine dyes described, for example, in JP KOKAI Nos. Sho 58-125246, 59-84356, 59-202829, and 60-78787; methine dyes, in JP KOKAI Nos. Sho 58-173696, 58-181690, and 58-194595; naphthoquinone dyes, in JP KOKAI Nos. Sho 58-112793, 58-224793, 59-48187, 59-73996, 60-52940, and 60-63744; squarylium dyes, in JP KOKAI No. Sho 58-112792; and cyanine dyes, in G.B. Patent No. 434,875.

[0055] As the preferable examples of the infrared absorbing agent, there can also be mentioned near infrared absorbing sensitizers disclosed in U.S. Patent No. 5,156,938; substituted arylbenzo(thio)pyrylium salts disclosed in U.S. Patent No. 3,881,924; trimethinethiapyrylium salts disclosed in JP KOKAI No. Sho 57-142645 (U.S. Patent No. 4,327,169); pyrylium compounds disclosed in JP KOKAI Nos. Sho 58-181051, 58-220143, 59-41363, 59-84248, 59-84249, 59-146063, and 59-146061; cyanine dyes disclosed in JP KOKAI No. Sho 59-216146; pentamethinethiapyrylium salts disclosed in U.S. Patent No. 4,283,475; and pyrylium compounds disclosed in JP KOKOKU Nos. Hei 5-13514 and 5-19702.

[0056] Furthermore, near-infrared absorbing dyes which are represented by formulas (I) and (II) in U.S. Patent No. 4,756,993 are also preferably used as the infrared absorbing agent.




[0057] Of the above-mentioned dyes, particularly preferable are cyanine dyes, squarylium dyes, pyrylium salts, and nickel thiolate complexes. Further, the cyanine dyes are especially suitable in the present invention, in particular, the following cyanine dyes represented by formula (5) are most preferable as the infrared absorbing agent.




[0058] In the above formula (5), X^1 represents a halogen atom, or X^2-L^1 or NL^2L^3 , in which X^2 is oxygen atom or sulfur atom, L^1 is a hydrocarbon group having 1 to 12 carbon atoms, and L^2 and L^3 are each independently a hydrocarbon group having 1 to 12 carbon atoms. R^1 and R^2 are each independently a hydrocarbon group having 1 to 12 carbon atoms, preferably a hydrocarbon group having 2 or more carbon atoms in light of the storage stability of a coating liquid for the image recording layer. More preferably, R^1 and R^2 may form a 5- or 6-membered ring in combination.

[0059] Ar^1 and Ar^2 in formula (5) may be the same or different, and are each an aromatic hydrocarbon group which may have a substituent. Y^1 and Y^2 , which may be the same or different, each represent sulfur atom or a dialkyl methylene group having 12 carbon atoms or less. R^3 and R^4 , which may be the same or different, are each a hydrocarbon group having 20 carbon atoms or less which may have a substituent. In this case, preferable examples of the substituent for the hydrocarbon group include an alkoxyl group having 12 carbon atoms or less, carboxyl group, and sulfo group. R^5 , R^6 , R^7 and R^8 , which may be the same or different, are each a hydrogen atom or a hydrocarbon group having 12 carbon atoms or less, preferably a hydrogen atom in light of availability of the raw material. Z^{1-} represents a counter anion, but Z^{1-} is not needed in the case where at least one of the groups represented by R^1 to R^8 has a sulfo group as a substituent. In consideration of the storage stability of a coating liquid for the image recording layer, it is preferable that Z^{1-} represent a halogen ion, perchlorate ion, tetrafluoroborate ion, hexafluorophosphate ion, or sulfonate ion, more preferably perchlorate ion, trifluoromethylsulfonate ion, or arylsulfonate ion.


[0060] Specific examples of the cyanine dyes represented by formula (5) which are suitably used in the present invention are shown below.




[IR-4]




[IR-5]







[IR-6]




[IR-7]







[IR-12]



[IR-13]



[IR-14]



[0061] As the pigments used as the infrared absorbing agent, there can be employed commercially available pigments, and other pigments described in "Color Index (C.I.) Binran (Color Index Handbook)", "Saishin Ganryo Binran (The Latest Pigment Handbook)" edited by Nihon Ganryo Gijutsu Kyokai (1977), "Saishin Ganryo Oyo Gijutsu (The Latest Pigment Applied Technology)" CMC Publishing Co., Ltd. (1986), and "Insatsu Ink Gijutsu (Printing Ink Technology)" CMC Publishing Co., Ltd. (1984).

[0062] Various kinds of pigments can be used in the present invention, for example, black pigment, yellow pigment, orange pigment, brown pigment, red pigment, violet pigment, blue pigment, green pigment, fluorescent pigment, metallic flake pigment, and polymer-binding pigment. Those pigments are explained in detail in JP KOKAI No. Hei 10-39509 (in paragraphs [0052] - [0054]), which is incorporated herein by reference. In particular, carbon black is most preferably used in the present invention.

[0063] In the image recording layer, it is preferable that the amount of the above-mentioned dye or pigment be in the range of 0.01 to 50% by weight, more preferably 0.1 to 10% by weight, based on the total weight of a solid content of the image recording layer. In the case where the dye is used as the infrared absorbing agent, the amount of the dye is most preferably in the range of 0.5 to 10% by weight. In the case where the pigment is used, the amount of the pigment is most preferably in the range of 1.0 to 10% by weight.

[0064] When the amount of the infrared absorbing agent is less than 0.01% by weight, the sensitivity will be lowered. On the other hand, when the amount exceeds 50% by weight, the obtained image forming material will cause scumming when made into a lithographic printing plate.

(D) Binder polymer

[0065] The image recording layer comprises a binder polymer to improve the film properties of the obtained image recording layer. A linear organic polymer is preferably used as the binder polymer. Any linear organic polymers can be used, and in particular, linear organic polymers that are soluble or swellable in water or a weak alkaline aqueous

solution may be selected because development with water or a weak alkaline aqueous solution can be carried out. The linear organic polymer may be selected in consideration of not only the performance as the film-forming agent for forming an image recording layer, but also the compatibility with a developing solution such as water, a weak alkaline aqueous solution, or an organic solution. For example, a water-soluble organic polymer allows development with water.

5 **[0066]** As the above-mentioned linear organic polymers, there can be mentioned radical polymers having carboxylic acid group in the side chain thereof as disclosed in JP KOKAI No. Sho 59-44615, JP KOKOKU Nos. Sho 54-34327, 58-12577, and 54-25957, and JP KOKAI Nos. Sho 54-92723, 59-53836, and 59-71048, i.e., methacrylic acid copolymers, acrylic acid copolymers, itaconic acid copolymers, crotonic acid copolymers, maleic acid copolymers, partially esterified maleic acid copolymers, and the like. Acidic cellulose derivatives having a carboxylic acid group in the side chain thereof can also be used. Further, addition reaction products prepared by adding a cyclic acid anhydride to a hydroxyl-group containing polymer are also useful as the binder polymers.

10 **[0067]** In particular, (meth)acrylic resins having a benzyl group or aryl group and a carboxyl group in the side chain thereof is suitably used in the present invention because such (meth)acrylic resins can offer an excellent balance of film strength, sensitivity and development performance.

15 **[0068]** Urethane binder polymers having an acid group as described in JP KOKOKU Nos. Hei 7-120040, 7-120041, 7-120042 and 8-12424, and JP KOKAI Nos. Sho 63-287944, Sho 63-287947, and Hei 1-271741 are advantageous in printing durability and suitability for low-power exposure because such urethane binder polymers exhibit significant strength.

20 **[0069]** Another examples of the water-soluble linear organic polymers useful as the binder polymers comprise polyvinyl pyrrolidone and polyethylene oxide. The use of alcohol-soluble nylon and polyether prepared from 2,2-bis-(4-hydroxyphenyl)-propane and epichlorohydrin is effective for increasing the strength of the cured film.

[0070] It is preferable that the binder polymer for use in the present invention have a weight-average molecular weight of 5,000 or more, and more preferably in the range of 10,000 to 300,000, and a number-average molecular weight of 1,000 or more, and more preferably in the range of 2,000 to 250,000. The polydispersity expressed as a ratio of the weight-average molecular weight to the number-average molecular weight is preferably 1 or more, and more preferably in the range of 1.1 to 10.

25 **[0071]** Such polymers may be in any form, for example, in the form of a random polymer, block polymer, or graft polymer. The binder polymer in the form of a random polymer is particularly preferable.

30 **[0072]** The binder polymers may be used alone or in combination. The binder polymer is suitably contained in the image recording layer in an amount of 20 to 95% by weight, preferably 30 to 90% by weight, based on the total weight of the solid content in a coating liquid for preparing the image recording layer. When the amount of the binder polymer is less than 20% by weight, an image area to be formed in the image recording layer will be lacking in strength. When the amount of the binder polymer exceeds 95% by weight, image formation will be impossible. It is preferable that the ratio of the amount of radical-polymerizable compound having ethylenically unsaturated double bond to the amount of linear organic polymer be in the range of 1/9 to 7/3 on a weight basis.

[Other components]

40 **[0073]** The image recording layer may further comprise a variety of compounds, if necessary, in addition to the above-mentioned components. For instance, a dye with a large absorption within the visible light range may be contained in the image recording layer as a coloring agent for the image area. Specific examples of such dyes are Oil Yellow #101, Oil Yellow #103, Oil Pink #312, Oil Green BG, Oil Blue BOS, Oil Blue #603, Oil Black BY, Oil Black BS, and Oil Black T-505 (all are products made by Orient Chemical Industries, Ltd.); Victoria Pure Blue, Crystal Violet (C.I.42555), Methyl Violet (C.I.42535), Ethyl Violet, Rhodamine B (C.I.145170B), Malachite Green (C.I.42000), and Methylene Blue (C.I. 52015); and dyes disclosed in JP KOKAI No. Sho 62-293247. In addition, pigments such as phthalocyanine pigments, azo pigments and titanium oxide are also preferably used as the coloring agent.

45 **[0074]** It is recommendable to add the above-mentioned coloring agent to the image recording layer because a clear distinction can be made between an image area and a non-image area after image formation. The amount of such a coloring agent is suitably in the range of 0.01 to 10% by weight based on the total weight of the solid content in a coating liquid for the image recording layer.

50 **[0075]** It is desirable to add a small amount of a heat-polymerization inhibitor to a coating liquid for the image recording layer in order to prevent the radical-polymerizable compound having ethylenically unsaturated double bond from causing undesired heat polymerization during the preparation of a coating liquid or the storage thereof. Specific examples of such a heat-polymerization inhibitor are hydroquinone, p-methoxyphenol, di-t-butyl-p-cresol, pyrogallol, t-butyl catechol, benzoquinone, 4,4'-thiobis(3-methyl-6-t-butylphenol), 2,2'-methylenebis(4-methyl-6-t-butylphenol), and N-nitroso-N-phenylhydroxylamine aluminum salts. The amount of the heat-polymerization inhibitor is preferably in the range of about 0.01 to about 5% by weight based on the total weight of the entire composition.

55 **[0076]** If necessary, the image recording layer coating liquid may further comprise higher fatty acids and derivatives

thereof such as behenic acid and behenic acid amide, and alcohols such as 1-docosanol to decrease the coefficient of friction of the image recording layer and therefore to improve scratch resistance. The coating liquid for the image recording layer may be dried after application so that the higher fatty acid derivatives or alcohols may be localized in a surface portion of the image recording layer to be obtained. The amount of the higher fatty acid derivatives is preferably in the range of about 0.1 to about 10% by weight based on the total weight of the entire composition.

[0077] Furthermore, the coating liquid for the image recording layer may further comprise a nonionic surfactant as disclosed in JP KOKAI Nos. Sho 62-251740 and Hei 3-208514 and an ampholytic surfactant as disclosed in JP KOKAI Nos. Sho 59-121044 and Hei 4-13149 to ensure the processing stability under the wider developing conditions.

[0078] Examples of the nonionic surfactant are sorbitan tristearate, sorbitan monopalmitate, sorbitan trioleate, stearic acid monoglyceride, and polyoxyethylene nonylphenyl ether.

[0079] Examples of the ampholytic surfactant are alkyl di(aminoethyl)glycine, alkylpolyaminoethyl glycine hydrochloride, 2-alkyl-N-carboxyethyl-N-hydroxyethylimidazolium betaine, and N-tetradecyl-N,N-betaine based surfactants such as a commercially available surfactant "AMOGEN K" (trademark), made by Dai-ichi Kogyo Seiyaku Co., Ltd.

[0080] The total amount of the above-mentioned nonionic surfactant and ampholytic surfactant is preferably in the range of 0.05 to 15% by weight, more preferably in the range of 0.1 to 5% by weight in the coating liquid for the image recording layer.

[0081] A plasticizer may be contained in the coating liquid for the image recording layer, if necessary, to impart proper flexibility to the coated layer. Examples of the plasticizer include polyethylene glycol, tributyl citrate, diethyl phthalate, dibutyl phthalate, dihexyl phthalate, dioctyl phthalate, tricresyl phosphate, tributyl phosphate, trioctyl phosphate, and tetrahydrofurfuryl oleate.

[0082] To prepare an image forming material for use in the present invention, the above-mentioned components may be dissolved in an appropriate solvent to prepare a coating liquid for the image recording layer, and the coating liquid may be coated on a proper substrate. Examples of the solvent used for preparation of the coating liquid are ethylene dichloride, cyclohexane, methyl ethyl ketone, methyl isobutyl ketone, methanol, ethanol, propanol, ethylene glycol monomethyl ether, 1-methoxy-2-propanol, 1-methoxy-3-propanol, 2-methoxyethyl acetate, 1-methoxy-2-propyl acetate, dimethoxyethane, methyl lactate, ethyl lactate, N,N-dimethylacetamide, N,N-dimethylformamide, tetramethylurea, N-methylpyrrolidone, dimethyl sulfoxide, sulfolane, γ -butyrolactone, toluene, and water. Those solvents may be used alone or in combination. In the coating liquid for the image recording layer, the concentration of all the components, that is, the solid contents of the components including additive components in the solvent is preferably in the range of 1 to 50% by weight.

[0083] The deposition amount of the image recording layer obtained after the coating liquid is applied and dried varies depending upon the application of the image forming material to be obtained, but typically in the range of 0.5 to 5.0 g/m² when the image forming material is used for a lithographic printing plate. The coating liquid for the image recording layer may be applied to the substrate by various coating methods, for example, bar coater coating, spin coating, spray coating, curtain coating, dip coating, air knife coating, blade coating, roll coating and the like. As the deposition amount is decreased, the apparent sensitivity increases, but the film properties of the image recording layer provided with the function of image formation are impaired.

[Substrate]

[0084] In the image forming material for use in the present invention, any dimensionally stable plate-shaped materials can be used as the substrate for supporting the previously mentioned image recording layer thereon. Preferably used are a sheet of paper; a laminated sheet prepared by covering paper with a thin layer of plastic, such as polyethylene, polypropylene, or polystyrene; a metal plate made of, for example, aluminum, zinc or copper; a plastic film made of, for example, cellulose diacetate, cellulose triacetate, cellulose propionate, cellulose butyrate, cellulose acetate butyrate, cellulose nitrate, polyethylene terephthalate, polyethylene, polystyrene, polypropylene, polycarbonate, or polyvinyl acetal; and a sheet of paper or plastic film to which the above-mentioned metals are attached or vapor deposited. A polyester film and an aluminum plate are particularly preferable as the substrate in the present invention.

[0085] In particular, it is preferable to use as the substrate for the image forming material an aluminum plate that is light and can be easily surface-treated, and is excellent in workability and corrosion resistance. In light of those requirements, aluminum materials in accordance with JIS 1050, JIS 1100, and JIS 1070, and aluminum alloy materials such as Al-Mg alloy, Al-Mn alloy, Al-Mn-Mg alloy, Al-Zr alloy, and Al-Mg-Si alloy are useful.

[0086] When the image forming material is obtained by providing the previously mentioned image recording layer on the aluminum plate which has been surface-treated to have a proper surface roughness, the image forming material can be subjected to making a lithographic printing plate. For the surface roughening treatment, mechanical roughening, chemical roughening and electrochemical roughening methods may be adopted alone or in combination. Prior to the surface roughening treatment, the aluminum plate may be subjected to anodization for improving wear resistance of the surface, or some treatment for enhancing the hydrophilic properties of the surface portion of the aluminum plate.

[0087] The surface treatment for finishing the aluminum substrate for use in the present invention will now be explained in detail.

[0088] The aluminum plate may be first subjected to degreasing, if required, before the surface roughening treatment, using a surfactant, organic solvent, or an aqueous alkaline solution to remove rolling oil from the surface of the aluminum plate. In the case where an alkaline solution is used for the degreasing, neutralization with an acidic solution, followed by desmutting may be carried out.

[0089] Next, the surface of the aluminum plate is roughened, that is, subjected to graining in order to improve the adhesion to the image recording layer and impart water retention properties to the non-image area to be formed. To provide the aluminum plate with a grained surface, mechanical surface-graining such as sandblasting, and chemical graining using an etching agent such as an alkali or acid, or mixtures thereof can be used. In addition, electrochemical graining is also effective, and other conventional graining methods can be also employed, for example, a method of attaching grains to an aluminum plate by means of an adhesive or the like, and a method of pressing an aluminum plate against a continuous belt or roller having a fine surface roughness to transfer such a fine grained pattern to the aluminum plate.

[0090] The above-mentioned methods for roughening the surface may be employed in combination. In this case, the order and the repetition number of the methods may be determined freely. Since smut is present on the grained surface of the aluminum plate, the aluminum plate may be appropriately washed with water or subjected to alkali etching for desmutting.

[0091] After the above-mentioned pre-treatment for the aluminum plate, an anodized film is generally provided on the aluminum plate by anodization to improve the wear resistance, chemical resistance and water retention properties.

[0092] Any material can be used as an electrolyte in the anodization of the aluminum plate so long as a porous anodized film can be formed on the surface of the aluminum plate. Typically, sulfuric acid, phosphoric acid, oxalic acid, hydrochloric acid, nitric acid, and mixtures thereof are used as the electrolyte. The concentration of the electrolyte is appropriately determined depending upon the kind of electrolyte. The operating conditions for the anodization cannot be particularly specified because they depend on the type of electrolyte. In general, it is proper that the concentration of the electrolyte be in the range of 1 to 80%, the liquid temperature be controlled to 5 to 70°C, the current density be in the range of 5 to 60 A/dm², the applied voltage be in the range of 1 to 100 V, and the time for electrolysis be in the range of 10 seconds to 5 minutes. The deposition amount of the anodized film is preferably 1.0 g/m² or more, and more preferably in the range of 2.0 to 6.0 g/m². When the deposition amount of the anodized film is less than 1.0 g/m², the printing durability will be insufficient, and the non-image area in the lithographic printing plate will be susceptible to scratches, and the scratches, if made on the printing plate, will be contaminated by ink during the printing operation, i.e., toning by the scratches on the non-image area will be possibly caused.

[0093] After completion of the anodization, the surface of the aluminum plate is subjected to a treatment such as silicate treatment to make the surface hydrophilic, if required.

[0094] The aluminum plate may be surface-treated with organic acids or salts thereof after anodization. Alternatively, an undercoating for providing the image recording layer may be applied to the aluminum plate.

[0095] The image forming material may further comprise an intermediate layer between the substrate and the image recording layer in order to improve the adhesion therebetween. For the purpose of enhancing the adhesion, the intermediate layer may comprise a diazo resin, a phosphonic acid compound, a phosphoric acid compound, or an aluminum compound such as aluminum alkoxide. The thickness of the intermediate layer is not particularly specified, but may be adjusted so that the intermediate layer can perform a homogenous bond forming reaction with the image recording layer, at the time of exposure. Typically, the deposition amount of the intermediate layer is preferably in the range of about 1 to 100 mg/m², more preferably in the range of 5 to 40 mg/m² on a dry basis.

[0096] After the substrate is surface-treated in the above-mentioned manner or the undercoating is applied thereto, a backcoating layer may be provided on the rear side of the substrate if necessary. It is preferable that the backcoating layer comprises organic polymer compounds as described in JP KOKAI No. Hei 5-45885, or metal oxides obtained from hydrolysis and polycondensation of inorganic or organic metal compounds as described in JP KOKAI No. Hei 6-35174.

[0097] In light of the application to a lithographic printing plate, the substrate has preferably a surface roughness in the range of 0.10 to 1.2 μm in terms of center-line mean roughness. When the surface roughness is less than 0.10 μm , the adhesion of the substrate to the image recording layer is decreased, which will considerably lower the printing durability. The substrate with a surface roughness of more than 1.2 μm will tend to cause scumming during the printing operation. The color density of the substrate is preferably in the range of 0.15 to 0.65 in terms of reflection density. When the reflection density is less than 0.15, image formation will be hindered by halation at the time of image exposure. In contrast to this, when the substrate has a reflection density of more than 0.65, images formed in the image recording material through development will become illegible, and therefore the operation of checking the printing plate cannot be conducted efficiently.

[0098] The negative type image forming material for use in the present invention can be prepared by the above-

mentioned method. Images can be recorded in the image recording material using infrared laser beams. In addition, the image forming material can also cope with thermal image formation using an ultraviolet lamp and a thermal head. In the present invention it is preferable that the image forming material be exposed to light images using solid lasers or semiconductor lasers capable of infrared radiation having wavelengths ranging from 760 to 1200 nm. The output power of the employed laser is preferably 100 mW or more, and the use of a multi-beam laser device is particularly preferable to curtail the exposure time. The exposure time is preferably 20 μ sec or less per picture element, and the energy applied to the image forming material is preferably in the range of 10 to 300 mJ/cm².

[0099] After completion of the image exposure using the lasers, the image recording material is developed with the alkaline developing solution as previously described.

[0100] Then, the image forming material is subjected to post-treatment using a washing water, a rinsing solution containing a surfactant, or a desensitizing solution containing gum arabic, starch derivatives or the like. The image forming material is thus made into a lithographic printing plate.

[0101] In recent years, the automatic processor for making a printing plate has been widely adopted to promote streamlining and standardization of the plate making operation in the plate-making and printing industries. The automatic processor generally includes a development area and a post-treatment area, provided with a unit for transporting a plate for preparing the printing plate, various liquid tanks, and a unit for spraying each liquid onto the plate. With the plate subjected to light exposure being horizontally transported in the automatic processor, development is carried out in such a manner that each liquid necessary for development is scooped up by a pump and sprayed through a spray nozzle onto the plate. There is also known another method that the plate is dipped in each processing liquid by causing the plate to pass through the liquid tank by the aid of a guide roll. In such an automatic operation, the respective replenishers are added to the liquid tanks according to the consumed amounts of the liquids and the operating time. Further, replenishment of those liquids can be automatically controlled by detecting the electroconductivity and pH value using sensors. Furthermore, the so-called disposable system is applicable to the above-mentioned automatic processor. To be more specific, the plate can be treated with substantially unused liquids, i.e., fresh liquids, and such liquids are thrown away after onetime use.

[0102] The lithographic printing plate thus obtained is ready for printing operation after application of a desensitizer if desired. To provide the printing plate with a still higher printing durability, the printing plate may be subjected to a post-exposure treatment and a burning treatment. When the lithographic printing plate is subjected to burning, it is preferable that the plate be treated with a plate cleaner before burning as described in JP KOKOKU Nos. Sho 61-2518, 55-28062, 62-31859 and 61-159655. More specifically, the treatment with a plate cleaner may be carried out by wiping the plate with a sponge or absorbent cotton impregnated with the plate cleaner, immersing the printing plate in a vat filled with the plate cleaner, or by coating the plate cleaner on the plate using an automatic coater. Further, when the deposition amount of the plate cleaner is made even using a squeegee or squeegee roll after application of the plate cleaner, more favorable results can be obtained. It is proper that the deposition amount of the plate cleaner be usually in the range of 0.03 to 0.8 g/m² on a dry basis.

[0103] The lithographic printing plate coated with a plate cleaner is dried when necessary, and then subjected to the burning treatment by heating the plate to high temperatures using a burning processor, for example, a commercially available burning processor "Model BP-1300" (trademark) available from Fuji Photo Film Co., Ltd. The heating temperature and heating time, which vary depending upon the kinds of components constituting the image area formed in the printing plate, are preferably controlled to 100 to 300°C and 1 to 20 minutes, respectively.

[0104] After completion of the burning treatment, the printing plate may appropriately be subjected to conventional treatments, such as washing with water, and coating of a desensitizing gum. When the printing plate has been treated with a plate cleaner containing a water-soluble polymer compound, the desensitizing treatment such as coating of the desensitizing gum is not necessary at this stage.

[0105] The lithographic printing plate thus prepared by the image forming method of the present invention is set in an offset press or the like to produce a large number of printed materials.

[0106] Other features of this invention will become apparent in the course of the following description of exemplary embodiments, which are given for illustration of the invention and are not intended to be limiting thereof.

Example 1

[Preparation of Substrate]

[0107] An aluminum web (JIS 1050) with a thickness of 0.30 mm was washed with trichloroethylene for degreasing, and subjected to surface-graining using the combination of a nylon brush and an aqueous suspension of 400-mesh pumice stone, and thereafter completely washed with water.

[0108] Then, the aluminum web was immersed in a 25% aqueous solution of sodium hydroxide maintained at 45°C for 9 seconds for etching. After that, the aluminum web was washed with water, and then immersed in a 2% aqueous

solution of HNO_3 for 20 seconds, followed by washing with water. The etched amount, that is, the amount of aluminum removed from the aluminum web by graining was about 3 g/m^2 .

[0109] After completion of the graining by etching, the aluminum web was subjected to anodization using 7% sulfuric acid as an electrolyte at a current density of 15 A/dm^2 , so that an anodized film was deposited on the surface of the aluminum web with a deposition amount of 3 g/m^2 . Thereafter, the aluminum web was subjected to a silicate treatment to ensure the hydrophilic properties of a non-image area to be formed in the printing plate. To be more specific, the aluminum web was caused to pass through a 1.5% aqueous solution of No. 3 sodium silicate maintained at 70°C over a period of 15 seconds. After that, the aluminum web was washed with water. The deposition amount of Si was 10 mg/m^2 .

[Formation of Undercoating Layer]

[0110] An undercoating with the following formulation was coated on the above-mentioned aluminum plate using a wire bar, and dried at 90°C for 30 seconds with a hot-air dryer, so that an undercoating layer was provided on the aluminum substrate. The deposition amount of the undercoating layer was 80 mg/m^2 on a dry basis.

(Formulation for undercoating)	
Aluminum alkyl acetoacetate diisopropylate "Aluminum Chelate M" (trademark) made by Kawaken Fine Chemicals Co., Ltd.	1.0 g
Methanol	100 g
Deionized water	10 g





[Formation of Image Recording Layer]

[0111] A coating liquid for image recording layer with the following formulation was coated on the above-mentioned undercoating layer using a wire bar, and dried at 120°C for 45 seconds with a hot-air dryer, so that an image recording layer was provided. An image forming material [P-1] for a lithographic printing plate was obtained according to the present invention. The deposition amount of the image recording layer was 2.0 g/m^2 on a dry basis.

(Formulation for image recording layer coating liquid)	
Onium salt [OS-7]	0.25 g
Polymerizable compound [RM-1]	0.60 g
Infrared absorbing agent [IR-13]	0.06 g
Polymer [PB-1]	1.40 g
Naphthalenesulfonate salt of Victoria Pure Blue	0.04 g
1-docosanol	0.01 g
Polymerization inhibitor ("IRGANOX 1010" (trademark), made by CIBA Specialty Chemicals Inc.)	0.005 g
Fluorine-containing surfactant ("MEGAFAC KF309" (trademark), made by Dainippon Ink & Chemicals, Incorporated)	0.03 g
Methyl ethyl ketone	10 g
γ -butyrolactone	5 g
Methanol	7 g
1-methoxy-3-propanol	5 g

[0112] The polymer (PB-1) for use in the above-mentioned formulation for the image recording layer coating liquid was prepared by first synthesizing a copolymer from (a) methacrylic acid, (b) acrylamide, and (c) benzyl methacrylate and thereafter reacting the obtained copolymer with (d) 3-chloro-2-hydroxypropyl methacrylate in the presence of a base and potassium iodide. The molar ratio of (a):(b):(c):(d) was 15:30:15:40, and the weight-average molecular weight of the obtained polymer (PB-1) was 100,000.

[0113] The compounds for use in the above formulation have the respective chemical structures shown below.



[Preparation of Developing Solutions]

[0114] Each developing solution was prepared as shown below.

(Developing solution No. 1 (pH = 10.0))

[0115] A developing solution No. 1 was prepared by dissolving 5% by weight of a surfactant represented by formula Y-1 and 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 10.0.

(Developing solution No. 2 (pH = 11.0))

[0116] A developing solution No. 2 was prepared by dissolving 5% by weight of a surfactant represented by formula Y-1 and 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 11.0.

(Developing solution No. 3 (pH = 12.0))

[0117] A developing solution No. 3 was prepared by dissolving 5% by weight of a surfactant represented by formula Y-1 and 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 12.0.

(Developing solution No. 4 (pH = 10.0))

[0118] A developing solution No. 4 was prepared by dissolving 5% by weight of a surfactant represented by formula

Y-1, 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent), 0.2% by weight of potassium carbonate and 0.5% by weight of potassium bicarbonate in water to have a pH value of 10.0.

(Developing solution No. 5 (pH = 10.0))

[0119] A developing solution No. 5 was prepared by dissolving 5% by weight of a surfactant represented by formula Y-1, 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent), and 0.3% by weight of triethanolamine in water to have a pH value of 10.0.

(Developing solution No. 6 (pH = 11.0))

[0120] A developing solution No. 6 was prepared by dissolving 5% by weight of a surfactant represented by formula Y-2 and 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 11.0.

(Developing solution No. 7 (pH = 11.0))

[0121] A developing solution No. 7 was prepared by dissolving 5% by weight of a surfactant represented by formula Y-3 and 0.2% by weight of ethylenediaminetetraacetic acid-4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 11.0.

[Evaluations of Developing Solution Compositions]

[0122] Evaluations of the developing solutions were carried out using a CTP output system available from Fuji Photo Film Co., Ltd., comprising a plate supplier (trademark: SA-L 8000), an exposure device (trademark: LUXEL T-9000 CTP), a plate conveyor (trademark: T-9000 CONVEYOR), an automatic processor (trademark: LP-1310H) and a stacker (trademark: ST-1160). A developer tank of the automatic processor was filled with each of the developing solutions No. 1 to No. 7, which was maintained at 30°C. Further, in the automatic processor, there were disposed a second tank provided with tap water and a third tank provided with a finishing gum solution prepared by diluting a finishing gum (trademark: FN-6 made by Fuji Photo Film Co., Ltd.) with water at a ratio of 1:1.

[0123] With the image forming material for lithographic printing plate [P-1] being set in the plate supplier of the CTP output system, continuous operation of light exposure and development using each of the developing solutions No. 1 to No. 7 was automatically conducted, and finally the plate was discharged into the stacker. The resolution was adjusted to 2400 dpi with 175 lines/inch at the time of exposure with the dot percent being changed within a range from 0.5 to 99.5%. It was visually observed with a magnifier whether dot formation on each printing plate was acceptable or not. The result was that the dot formation was satisfactory at any dot percent from 0.5 to 99.5% in all cases.

[0124] Each of the lithographic printing plates thus obtained and a commercially available black offset ink "GEOS-G", (trademark), made by Dainippon Ink & Chemicals, Incorporated were set in a printing press "Model R201" (trademark), made by MAN Roland Druckmaschinen AG, to carry out a printing operation. In the case where the printing plates obtained through the development with the developing solutions Nos. 1, 2, 4 and 5 were subjected to the printing operation, there occurred printing failure when 100,000 prints were made. When the printing plates obtained through the development with the developing solutions Nos. 3, 6 and 7 were used, printing failure was caused when 90,000 prints were made.

Example 2

(Evaluations of Change in Developing Solutions with Time)

[0125] The image forming material [P-1] for lithographic printing plate prepared in Example 1 was set in the same CTP output system as in Example 1, and 1000 m² of the image forming material [P-1] was subjected to development over a period of 3 weeks, with the developer tank of the automatic processor being filled with each of the developing solutions Nos. 1, 4 and 5. The image formation on the image forming material was examined after completion of development processing of 10 m², 500 m², and 1000 m² of the image forming material. The result was that dot formation was satisfactory at any dot percent ranging from 0.5 to 99.5% at any stage with all the developing solutions Nos. 1, 4 and 5. After completion of the development, each developing solution was allowed to stand for one week. One week later, the developer tank was drained and it was examined whether developing sludge was deposited on the tank or not. No deposition was observed with all the developing solutions Nos. 1, 4 and 5.

[Comparative Example 1]

[0126] The procedure for image formation on the image forming material [P-1] in Example 1 was repeated except that a comparative developing solution No. 1 shown below was used for development. Thus, a comparative lithographic printing plate of negative-type was obtained.

(Comparative developing solution No. 1 (pH = 11.0))

[0127] A comparative developing solution No. 1 was prepared by dissolving 5% by weight of sodium dibutyl naphthalenesulfonate (anionic surfactant) and 0.2% by weight of ethylenediaminetetraacetic acid 4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 11.0.

(Evaluations)

[0128] The images formed in the comparative lithographic printing plate were visually observed with a magnifier in terms of dot formation. The result was that the dot formation was satisfactory at a dot percent ranging from 2 to 98%, although minute dots were not formed at a dot percent of 0.5%, 1%, 99% and 99.5%.

[0129] Then, the comparative lithographic printing plate was set in the same printing press to carry out a printing operation in the same manner as in Example 1. In this case, there occurred printing failure when 70,000 prints were made.

[0130] The comparative developing solution No. 1 was evaluated in terms of deterioration with time in the same manner as in Example 2. The image forming material [P-1] for lithographic printing plate prepared in Example 1 was set in the same CTP output system as in Example 1, and 1000 m² of the image forming material [P-1] was subjected to development with the comparative developing solution No. 1 over a period of 3 weeks. The image formation on the image forming material was examined after completion of development processing of 10 m², 500 m², and 1000 m² of the image forming material. The result was that dot formation was satisfactory at a dot percent ranging from 2 to 99.5% after the completion of processing of 10 m², and dot formation was acceptable at a dot percent ranging from 2 to 98.5% after the completion of processing of 500 m² and 1000 m². In other words, it was confirmed that reproducibility of shadow portions was lowered with time. After that, the comparative developing solution No. 1 was allowed to stand for one week. One week later, the developer tank was drained and it was examined whether developing sludge was deposited on the tank or not. Considerable deposition of developing sludge was observed.

[Comparative Example 2]

[0131] The procedure for image formation on the image forming material [P-1] in Example 1 was repeated except that a comparative developing solution No. 2 shown below was used for development. Thus, a comparative lithographic printing plate of negative-type was obtained.

(Comparative developing solution No. 2 (pH = 12.5))

[0132] A comparative developing solution No. 2 was prepared by dissolving 5% by weight of sodium dibutyl naphthalenesulfonate (anionic surfactant) and 0.2% by weight of ethylenediaminetetraacetic acid 4Na salt (chelating agent) in water and adding potassium hydroxide to the aqueous solution to have a pH value of 12.5.

(Evaluations)

[0133] The images formed in the comparative lithographic printing plate were visually observed with a magnifier in terms of dot formation. The result was that the dot formation was satisfactory at a dot percent ranging from 5 to 99.5%, although minute dots were not formed at a dot percent of 0.5%, 1%, 2%, 3% and 4%.

[0134] Then, the comparative lithographic printing plate was set in the same printing press to carry out a printing operation in the same manner as in Example 1. In this case, there occurred printing failure when 40,000 prints were made.

[0135] As previously mentioned, the present invention can provide an excellent image forming method using a negative-type image forming material, capable of forming images therein by direct transfer of digital data from computers or the like using infrared lasers. More specifically, the above-mentioned image forming method can provide a lithographic printing plate with excellent image forming properties and high printing durability even though the image forming material is not subjected to heat treatment after light exposure. Further, the image forming method of the present invention makes it possible to stably continue the process of development for an extended period of time without any

deterioration in developing performance with time, which has been considered to result from the properties of a developing solution to be employed, and without any deposition of developing sludge.



Claims

1. An image forming method comprising the steps of exposing a negative type image forming material to infrared laser imagewise, which image forming material comprises a substrate and an image recording layer formed thereon, comprising (A) a radical generator, (B) a radical-polymerizable compound, (C) an infrared absorbing agent, and (D) a binder polymer; and developing the image forming material with an alkaline developing solution comprising at least one nonionic aromatic ether based surfactant represented by the following formula:



wherein X is an aromatic ring; Y represents a single bond or an alkylene group having 1 to 10 carbon atoms; A and B, which are different from each other, represent $-CH_2CH_2O-$ or $-CH_2CH(CH_3)O-$; and n and m each represent 0 or an integer of from 1 to 100, provided that n and m are not 0 at the same time.


2. The method of claim 1 wherein the nonionic aromatic ether based surfactant is at least one selected from the group consisting of compounds represented by the following formula (I-A) or (I-B):




wherein R_1 and R_2 each represents hydrogen atom or an organic residue having 1 to 100 carbon atoms; p and q each represents an integer of 1 or 2, Y_1 and Y_2 each represents a single bond or an alkylene group having 1 to 10 carbon atoms; r and s each represents 0 or an integer ranging from 1 to 100 provided that r and s are not 0 at the same time; r' and s' each represents 0 or an integer ranging from 1 to 100 provided that r' and s' are not 0 at the same time.

3. The method of claim 2 wherein R_1 and R_2 each represents hydrogen atom or an organic residue selected from aliphatic hydrocarbon groups, aromatic hydrocarbon groups, alkoxy, aryloxy, N-alkylamino, N,N-dialkylamino, N-arylamino, N,N-diarylamino, N-alkyl-N-arylamino, acyloxy, carbamoyloxy, N-alkylcarbamoyloxy, N-arylcarbamoyloxy, N,N-dialkylcarbamoyloxy, N,N-diarylcarbamoyloxy, N-alkyl-N-arylcarbamoyloxy, acylamino, N-alkylacylamino, N-arylacylamino, acyl, alkoxy-carbonylamino, alkoxy-carbonyl, aryloxy-carbonyl, carbamoyl, N-alkylcarbamoyl, N,N-dialkylcarbamoyl, N-arylcarbamoyl, N,N-diarylcarbamoyl, N-alkyl-N-arylcarbamoyl, polyoxyalkylene groups, the above exemplified organic residue to which a polyoxyalkylene group bonds.
4. The method of claim 2 wherein R_1 and R_2 each represents hydrogen atom or an organic residue selected from linear or branched alkyl group having 1 to 10 carbon atoms; alkoxy group, alkoxy-carbonyl group, N-alkylamino group, N,N-dialkylamino group, N-alkylcarbamoyl group, acyloxy group and acylamino group which have 1 to 10 carbon atoms; polyoxyalkylene group wherein the number of repeating unit is from 5 to 20; aryl group having 6 to 20 carbon atoms; and the aryl group to which a polyoxyalkylene group bonds with the number of repeating unit being from 5 to 20.
5. The method of claim 2 wherein r and r' each represents an integer of from 3 to 50, and s and s' each represents 0 or an integer of from 1 to 10.


6. The method of claim 1 wherein the alkaline developing solution further comprises an alkaline agent.
7. The method of claim 1 wherein the alkaline developing solution further comprises a chelating agent selected from polyphosphates, polyaminocarboxylic acids and salts thereof, and organophosphonic acids and salts thereof.
8. The method of claim 1 wherein the alkaline developing solution has a pH of from 10.0 to 12.8.
9. The method of claim 1 wherein (A) a radical generator is selected from the group consisting of onium salts, s-triazine compounds having a trihalomethyl group, peroxides, azo based polymerization initiators, azido compounds and borate salts.
10. The method of claim 9 wherein the onium salt is selected from the group consisting of the compounds represented by the formula (1), (2) or (3):



wherein Ar¹¹ and Ar¹² are each independently an aryl group having 20 carbon atoms or less, and Z¹¹⁻ represents a counter ion,




wherein Ar²¹ is an aryl group having 20 carbon atoms or less, and Z²¹⁻ represents a counter ion,



wherein R³¹, R³², and R³³ are each a hydrocarbon group having 20 carbon atoms or less, and Z³¹⁻ represents a counter ion.

11. The method of claim 1 wherein (B) a radical-polymerizable compound is selected from esters compounds of an unsaturated carboxylic acid and an aliphatic polyhydric alcohol, amide compounds of an unsaturated carboxylic acid and an aliphatic polyvalent amine, and urethane based addition-polymerizable compounds.
12. The method of claim 1 wherein (C) an infrared absorbing agent is selected from the group consisting of cyanine dyes, squarylium dyes, pyrylium salts, and nickel thiolate complexes.
13. The method of claim 1 wherein the cyanine dye is selected from the group consisting of the compounds represented by the formula:



wherein X¹ represents a halogen atom, or X²-L¹ or NL²L³, in which X² is oxygen atom or sulfur atom, L¹ is a hydrocarbon group having 1 to 12 carbon atoms, and L² and L³ are each independently a hydrocarbon group having 1 to 12 carbon atoms; R¹ and R² are each independently a hydrocarbon group having 1 to 12 carbon atoms; Ar¹ and Ar² may be the same or different, and are each an aromatic hydrocarbon group which may have a substituent; Y¹ and Y², which may be the same or different, each represent sulfur atom or a dialkyl methylene group having 12 carbon atoms or less; R³ and R⁴, which may be the same or different, are each a hydrocarbon group having 20 carbon atoms or less which may have a substituent; R⁵, R⁶, R⁷ and R⁸, which may be the same or different, are each a hydrogen atom or a hydrocarbon group having 12 carbon atoms or less; Z¹⁻ represents a counter anion, but Z¹⁻ is not needed in the case where at least one of the groups represented by R¹ to R⁸ has a sulfo group as a substituent.